

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas
7-19-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Holy Cross "A" Well No. 4

Location NE NW SE Sec. 4 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3442'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2:45 P Day 14 Month 7 Year 1971

The above well was plugged as follows:

Total Depth 3442' 8 5/8 csg set at 240' cwc 175 sk.

5 1/2 csg set at 3442' cw 175 sk cmt.

5 1/2 csg PBTB 3411' with top perf. (3086)

Set 5 1/2 wood plug at 3000' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (2950-3000)

Cutoff and recovered 610' of 5 1/2 csg.

Pumped down 8 5/8 csg with 18 sk gel & water W/3 sk hulls (780-TD) 70 sk 50-50 poz

6% gel (490-780) 7 sk gel & water (210-490) 50 sk 50-50 poz 6% gel. (0-210)
release plug and pumped

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messary
Well Plugging Supervisor

INVOICED

DATE 7-20-71

INV. NO. 4018-4