

15-143-30158-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1966

CONSERVATION DIVISION
WICHITA, KANSAS

6/14/66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Max Cohen Oil Co.

Complete Address: Box-13528 Phoenix, Arizona

Lease Name Griffith Well No. 1

Location E/2 SW NW Sec. 13 Twp. 9 Rge. 16 (E) (W) X

County Rooks Total Depth 3500

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: D & D Drilling Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7³⁰ A Day 13 Month 6 Year 1966

The Above well was plugged as follows:

RTD 3500 8 5/8 set at 79 Ft. cw 50 sc. cem.

Gunned pits, circulated heavy mud, set cementing plug at 540 Ft. and displaced 25 sax cement thru drill pipe. Heavy mud to 150 Ft. set cementing plug and displaced 20 sax cement thru drill pipe. Heavy mud to 40 Ft. set cementing plug, 1/3 sax hulls, and 10 sax cement to base of cellar. Plugged rat hole with 2 sax cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio Massup
Well Plugging Supervisor

DATE 6/14/66

INV. NO. 3403-W