

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163-03820-0278978 (this well)

6/23/78  
RECEIVED  
CORPORATION COMMISSION  
JUN 23 1978  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A H. Krueger Jr.

Complete Address 209 Circle Drive, Hays, Kansas 67601

Lease Name Brown Well No. 4

Location SW NW SE Sec. 14 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3497'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 5:15 P Day 21 Month 6 Year 1978

The above well was plugged as follows:

Total Depth 3497' 8 5/8 csg set 125' cwc 100 sk.

5 1/2 csg set 2497' cw 135 sk cem. PFS. (3240-3250')

Filled 5 1/2 csg W/sd (3497'-3200') dumped 4 sk cem W/dump bailer. (3200'-3170')

Cutoff & recovered A/600' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls- followed with 70 sk 50-50 poz 6% -displaced with 5 sk gel & water & capped

with cementing plug & 50 sk 50-50 poz 6% & shutin. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-26-78  
INV. NO. 7565.6

Signed: Leo Massey  
Well Plugging Supervisor