

4-041601

8-16

15-163-19199-00 01

E-25,262

API number: 15- -

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW /4 SEC. 13, 09 S, 16 W
990 feet from S section line
4290 feet from E section line

Operator license# 6597 Lease Dorr well # B-2

Operator: A.H. Kruger Oil Company County Rooks

Address: 211 Circle Drive Well total depth 3480 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 158 feet

113.10

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 16 Month: August Year: 94

Plugging proposal received from: A.H. Kruger, Jr.

Company: A.H. Kruger Oil Company Phone: _____

Were: 4 1/2" casing set @ 3470' w/150 sxs. cmt. Perf. @ 3122' - 3340'.
Annulus squeezed with 950 sxs. cement. Verified with bond log.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis Hamel - Don Butcher
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:00P.M., Day: 16, Month: August, Year: 94

Actual plugging report: Bottom plug: 30 sxs. with 100# hulls. Displaced to base of packer at 3100'. Pressured to 1400#. Released packer and pulled same. R.I.H. with tubing. Spotted 90 sxs. cement to circulate at surface. Pulled tubing and squeezed 30 sxs. cement down casing. Max. 300#.

Remarks: Tubing annulus filled with anguard.
Condition of casing(in hole): GOOD X BAD _____ Anhy. plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING X, CASING _____ Elevation: _____ GL _____

I did X / did not [] observe the plugging. Dennis L. Hamel

DATE 9-8-94
BY. NO. 41149

17D.

(agent)
Form CP-2/3