

4-041527

9-13

API number: 15-163-30231-00-20 - 11-20-66

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW SW /4 SEC. 13, 09 S, 16 W
2310 feet from S section line
4950 feet from E section line

Operator license# 6597

Lease Dorr well # 1-C 2AD

Operator: A.H. Krueger, Jr.

County Rooks

Address: 211 Circle Dr.
Hays, Kansas 67601

Well total depth 3466 feet ^{112.64}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 136 feet
w/150 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 13 Month: September Year: 93

Plugging proposal received from: A.H. Krueger, Jr.

Company: A.H. Krueger, Jr. Phone:

Were: 4 1/2" casing set @ 3466' w/250 sx. cement. Perf. @ 2958'-3375'.
Salt @ 1995' - Anhy. @ 1295' - Dakota @ 700'. Casing squeezed @ 2607' -
1100' - 770' - 700' with cement NA. Additional holes in casing @ 870' -
900' and 2660' - 2390'.
Ordered 200 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 13, Month: September, Year: 93

Actual plugging report: Run in hole with tubing. Spot 50 sx. cement
with 100# hulls @ 3300'. Pull to 2200'. Spot 50 sx. cement with 100#
hulls. Pull to 1100' spot 60 sx. cement with 100# hulls to circulate
cement. P.O.O.H. with tubing, squeezed casing with 25 sx. cement.
Max. 300#. S.I. 300#. Pumped down 8 5/8" S.P. 25 sx. cement with
100# hulls. Squeezed to 600# max.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING X, CASING . Elevation:

I did] did not] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1993
Dennis L. Hamel
AD
(agent) CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INVOICED
NOV 17 1993
DATE
INV. NO. 39217