

6 040979

To:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15-11-22-15-163-03757-00-01 1939

NW NE NW, SEC. 14, T 9 S, R 16 WYE

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Operator: Harold Kruger Co.
 Name & Box 247
 Address

Natoma, Ks. 67651

feet from S section line

feet from E section line

Lease Name Tatkenhorst Well # A-1

County Rooks 112.00

Well Total Depth 3446 feet

Conductor Pipe: Size feet

Surface Casing: Size 12" feet 54' cwc

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 2 2 Month: Nov Year: 19 88

Plugging proposal received from Dean Wineland

(company name) Harold Kruger Co. (phone)

were: 7" casing set at 3237' w/NA. Top perf at K.C. Perf anhy at 1350' and base Dakota
 at 775'. Base S.P. at 60'. W.L.M. to 3125'. Ordered 500 sks 65/35 Poz 10% Gel w/1/2"
 F.C. plus 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 6:00 PM Day: 22 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 7" casing. 150 sks cement. Disp w/52 Bbls of H2O,

Pressure to 750#. Perf casing at 1350'. Ptmpe 75 sks cement, disp w/28 bbls.

H2O, pressure to 400#. Perf casing at 775'. Pumped 150 sks cement. Perf casing at

60'. Circ cement to surface w/125 sks cement.

Remarks:

(If additional description is necessary, use BACK of this

I (could not) observe this plugging.

DATE 1-5-89

INV. NO. 23493

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel

FORM CP-2/3
Rev. 01-84

RECEIVED
 STATE CORPORATION COMMISSION
 12/20/88
 DEC 20 1988

CONSERVATION DIVISION
 Wichita, Kansas