

1-14-88

R

6 031030

API NUMBER 15-163-21,319-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW, SEC. 14, T 9 S, R 16 W/E
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4832

Lease Name Rathbun Well # 1

Operator: Hamlin Oil Operations, Inc.
Name & Address: P.O. Box 781626
Wichita, Kansas 67278

County Rooks 116.03
Well Total Depth 3570 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 14 Month: 1 Year: 19 88

Plugging proposal received from Ronnie
(company name) Kelso (phone) _____

were: 8 5/8 set at 260' with 165 sx cwc 4 1/2" set at 3562' with 150 sx PBDT 3310'
Perf 3260-62 order sand and com. cmt. Pull Pipe, Order 200 sx
ATL 65/35 poz 10% gel 2% dicel cement blend 5 sx hulls Allied.
Cement Co. Jerry's Tank Service Water.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45 AM Day: 14 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT Sand Bottom to 3210' with 4 sx com. cmt. on sand with bailer
recovered 2100' of 4 1/2" casing.

Squeezed 8 5/8 csg. with 200 sx cement blend with 5 sx hulls mixed in.
Max. PSI 300 # close in PSI 200 # plug Complete.

RECEIVED
STATE CORPORATION COMMISSION
FEB 05 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 2-F-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19772

Carl Goodrow