

6 040834

12-8-87

API NUMBER 15-163-30237-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S/2 NW, SEC. 14, T 9 S, R 16 W/E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

Lease Name Tatkenhorst Well # <sup>A REC CAP</sup> 1

County \_\_\_\_\_ Rooks 114.34

Well Total Depth 3518 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 140' cwc

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Operator: Kruger Brother Oil Co.

Name & Address Natoma, Kansas 67651

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing Co. License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: 12:30PM Day: 8 Month: Dec Year: 19 87

Plugging proposal received from Dean Wineland

(company name) Kruger Oil Co. (phone) \_\_\_\_\_

were: 4 1/2" csg set at 3517' w/T.D.C. at 2750';

Perf at 2964' - 3170'. Perf csg to plug at 1250'; 3 holes, and base

Dakota at 700' (3 holes).

Ordered 200 sks. 65/35 Poz 10% Gel 2% Lite w/1/4# Flocele per sx. cmt. plus

6 sks Hulls.

Plugging Proposal Received by D. L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 12:30PM Day: 8 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT

Pumped in 4 1/2" csg 25 sks cmt w/Flocele plus 135 sks cmt w/Flocele and Hulls.

Max PSI 400# S.I. 250#

Pumped in 8 5/8" S.P. 40 sks cmt w/Flocele and Hulls.

Max 300# S.I. 250#.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel

JAN 18 1988

observe this plugging.

INVOICED

DATE 1-20-88

INV. NO. 19602