

6 070414

API NUMBER 15-163-22, 789-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW-SE-NE, SEC. 15, T. 9 S, R. 16 W/E
2,970 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4538

Lease Name Casey Well # 1-15

Operator: Boswell Energy Corporation

County Rooks 122.33

Name & Address 6600 North Harvey, # 100

Well Total Depth 2764 feet

Oklahoma City, Oklahoma

Conductor Pipe: Size 0 feet

R. Kent Pinson 73116

Surface Casing: Size 8 5/8 feet 209 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Drilling Inc License Number 8241

Address Box 506 45 Kansas, Russell, Kans. 67665

Company to plug at: Hour: 1:30 AM Day: 1st Month: Nov. Year: 19 85

Plugging proposal received from Nick Kreutzer

(company name) Emphasis Drilling Inc. (phone) 405-840-4073

were: 8 5/8" - 209' SP. CUC 1/150 SK CNT, 60/40 Formix Gel-Ca-Cl - 2% 3% - By Allied Int.

Order 210 60/40 Formix Gel-Ca-Cl - 1 SK Cello Slake and 8 5/8" Plug.

Spot with Drill Stem, Recondition Hole (viscosity) Heavy Mud Between All Plugs.

No Circulation Problems, Mud Condition 42 viscosity, 9.8 weight, 4.8 loss.

Seabuckle @ 3785' EIV. 2111 - Inhydrate 1340

Plugging Proposal Received by Marion Schmidt
DBIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:30 AM Day: 1st Month: Nov. Year: 19 85

ACTUAL PLUGGING REPORT Ordered 210 60/40 Formix Gel-Ca-Cl - 1 SK Cello Slake and 8 5/8" Plug

Spot with Drill Stem, Recondition Hole Heavy Mud Between All Plugs

1st Plug @ 3700' 1/25 SK CNT 2nd Plug @ 1370' 1/25 SK CNT

3rd Plug @ 880' 1/100 SK 1/4 SK Cello Slake, 4th Plug @ 240' 1/40 SK CNT

5th Plug Solid Bridge @ 40' to 0' 1/10 SK CNT, 10 SK In Pat Hole (cir)

Cemented by allied Int

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 26 1985

INV. NO. 11214

RECEIVED

STATE CORPORATION COMMISSION

NOV 26 1985

CONSERVATION DIVISION

Signed Marion Schmidt
DBIC (TECHNICIAN)