

8-27

4-070055

15-163-03604-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - N/A

C SW SW /4 SEC. 16, 09 S, 16 W  
660 feet from S section line  
~~660~~ 4620 feet from E section line

Operator license# 6569  
Operator: Carmen Schmidt  
Address: P.O. Box 47  
Great Bend, Kansas 67530

Lease: Dorr Unit Well # 501  
County: Rooks 110.21  
Well total depth 3391 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 235 feet  
W/235 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 27 Month: August Year: 1997

Plugging proposal received from: Curtis Hitschman

Company: Carmen Schmidt Phone: 316-793-5100

Were: Run tubing to 3305' and plug well on the lay out with tubing according to State recommendations.

Plugging Proposal Received by: Richard Williams

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:30 P.M., Day: 27, Month: August, Year: 1997

Actual plugging report: LK Wireline perforated base of salt section at 1860'. Anhydrite at 1270' and Dakota at 550'. Fluid level at 1600'. PSTD 3391'. Perfs at 3305' - 3391'. Ran tubing in hole to 3310'. Allied pumped 50 sxs 60/40 pozmix - 10% gel with 1/4# flow seal and 200# hulls. Pulled tubing to 2000'. Allied pumped 110 sxs cement with 200# hulls circulated to pit. Pulled tubing out and hooked-up to 4 1/2" casing, pumped 20 sxs. Max. P.S.I. 800#. S.I.P. 400#. Hooked-up 8 5/8" and pumped 30 sxs with 100# hulls. Max. p.S.I. 500#. S.I.P. 350#.

Remarks:  
Condition of casing(in hole): GOOD BAD X  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING  
Anhy.plug: YES X NO  
Dakota plug: YES X NO  
Elevation: 2026 GL

I did [ X ] / did not [ ] observe the plugging.

Richard Williams  
KANSAS CORP COMM  
RECEIVED  
9/4/97  
Form CP-2/3

INVOICED

DATE 9-8-97

INV. NO. 48932

8-27