

2-22

4-041567

15-163-03605-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 5-29-47

SW NW SW /4 SEC. 16 , 09 S, 16 W
1650 feet from S section line
4950 feet from E section line

Operator license# 31233

Lease Dorr Unit well # 502

Operator: Gold Petroleum, Inc.

County Rooks

Address: 3917 So. Peachway
Denver, Colorado
80237-0242

Well total depth 3352 feet ^{108.94}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 239 feet
w/150 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 22 Month: February Year: 94

Plugging proposal received from: Carl Zimmerman

Company: Gold Petroleum, Inc. Phone:

Were: 4 1/2" casing set @ 3351' w/150 sxs. cement. Perfs. at
3120' - 3334'. Perf anhy. at 1270'. Perf 02-21-94 at 1270'. Squeeze
at 2030' - 2520' with 400 sxs. plus squeeze at 767' with 500 sxs.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M. Day: 22, Month: February, Year: 94

Actual plugging report: R.I.H. with tubing to 3064'. Spot 50 sxs.
cement with 200# hulls. Pull to 2000'. Spot 60 sxs. cement plus 200#
hulls to circulate at surface. P.O.O.H. with tubing. Squeeze casing
with 40 sxs. cement. Max. 600#. S.I.P. 400#. Hooked-up to 8 5/8"
S.P. Squeeze 50 sxs. cement with 100# hulls. Max 300#. S.I.P. 100#.

MAR 01 1994

CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE MAR 08 1994

INV. NO. 40075

2-22