

To:

6 030913

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-03711-00-00  
6-6-53

SE SE SW, SEC. 16, T 9 S, R 16 WR

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Dorr Well # 505

Operator: Cities Service Oil and Gas Corp.

County Rooks 112.45

Name & Address 3545 N.W. 58th St.

Well Total Depth 3460 feet

Oklahoma City, Ok. 73112

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 231

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Hays, Kansas 67601

Company to plug at: Hour: AM Day: 18 Month: 6 Year: 19 87

Plugging proposal received from Rick Brower

(company name) Cities Service (phone) \_\_\_\_\_

were: 8 5/8 set @ 231' w/175 sx. 5 1/2 set @ 3460 w/175 sx P.B.T.D. 3451

D.V. Tool @ 1314' w/ 345 sx. CWC. Perf. 3170' - 3436 9 shots

Order 200 sx econolite 65/35 poz 10% gel 2% dicel Halliburton Cmt. Blend

6 sx hulls.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 AM Day: 18 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Mix and pump on 8 5/8" - 5 1/2" Annulus would not take. Squeeze down 5 1/2" w/ 4 sx hulls 25 sx cmt. blend.

2 hulls w/ 155 sx cmt blend. Max. P.S.I. 500 # close in 500 # plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
7/16/87 JUL 16 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If you did not observe this plugging.

DATE 7-20-87

Signed Carl Goodrow  
(TECHNICIAN)

INV. NO. 12508