

6 100262

API NUMBER 15-No 3-21902-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE 4, SEC. 18, T. 29 S, R. 16 (W) 16

330 feet from W/S section line

2310 feet from W/E section line

Lease Name Colahan Well # 1

County Rooks 112.13

Well Total Depth 3450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 248

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.

Name & Address 155 N. M. RT

200 W. Douglas #300 1000

Wichita, Kansas 67202-1801

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor company License Number _____

Address _____

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Alan Dick

(company name) TXO (phone) _____

were: pump 200 sx cmt down 4 1/2" casing & 150 sx cmt down annulus.

4 1/2" set at 3449'

perf @ 3166-3447

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 AM Day: 10 Month: Dec Year: 19 86

ACTUAL PLUGGING REPORT Perf 4 1/2" @ 1265' & 380'. Pump down 25 sx cmt followed by 2 sx hulls then 175 sx cmt mix with 25 sx hulls. Pump down annulus 150 sx cmt mixed with 15 sx hulls. Maximum pressure on 4 1/2" - 600 psi, max pressure on annulus 500 psi - shut in pressure 300 psi.

RECEIVED STATE CORPORATION COMMISSION

DEC 15 1986 12/15/86

order 350 sx of Econolite (65/35 posmix w/10% gel & 2% diesel)

Remarks: Cemented by Allied instructions given by Dennis Hamel
(If additional description is necessary, use BACK of this form.)

Did not observe this plugging.

DATE 12-15-86

Signed David K. [Signature] (TECHNICIAN)

REV. NO. 15634

12-10 FEB 10 1987