

To: 6 040780
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-22 264
R
API NUMBER 15-163-01461-00-01
SE/4, SEC. 20, T 9 S, R 16 (W/E)
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5769

Lease Name Overhulser Well # 3

Operator: Kruger Oil Co.
Name & Address Box 247
Natoma, Kansas 67651

County Rooks 112.45
Well Total Depth 3460 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 198' w/140 sks.

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cmt. Co. License Number _____

Address Russell, Kansas

Company to plug at: Hour: 1:15PM Day: 22 Month: July Year: 1987

Plugging proposal received from Dean Wineland

(company name) Kruger Oil Co. (phone) _____

were: 5 1/2" csg set at 3460' w/150 sks cmt.

Perf at 3230' - 3391'. Fish in hole to 1400' top. Holes in csg from 400' to 1400'.

Ordered 350 sks 65/35 Poz 10% Gel w/1/4# Flocele and 8 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1:15 PM Day: 22 Month: July Year: 1987

ACTUAL PLUGGING REPORT

Ran tubing to 1400'. Pumped 50 sks cmt. plus 50 add cmt w/3 sks Hulls.

Cmt circ to surface. Pulled tubing; pmpd add 200 sks w/3 sks Hulls in 5 1/2" csg.

Max Psi. 500# Shut in 100#

Pumped in 8 5/8" s.P. 50 sks cmt. w/2 sks Hulls.

Max 250# Psi. Shut in 100# Psi.

Remarks: ck cmt top - ok
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORP. COMMISSION
SEP 4 1987
Wichita, Kansas

INVOICED

DATE 9-15-87
INV. NO. 18114
observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel