

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01468-00-00  
Spot: CNWSWSW Sec/Twnshp/Rge: 1-9S-17W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: HRABE A Well Number: 3  
County: ROOKS Total Vertical Depth: 3485 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet: 130 <sup>KLL</sup> <sub>CHP</sub> \$113.26  
Surface Casing: Size 8.625 feet: 303 140 SX CMT  
Production: Size 5.5 feet: 3485 200 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/27/2002 1:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perf 5 1/2" casing at 1275' and 725'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/27/2002 4:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing to 2225' - spotted 50 sxs cement with 300# hulls.  
Pulled to 1314' - spotted 50 sxs cement with 250# hulls.  
Pulled tubing to 751' and spotted 120 sxs cement to circulate at surface.  
POOH with tubing and squeezed 5 1/2" casing with 30 sxs cement plus 100# hulls in cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
8 5/8" S.P. - pressured up to Max. P.S.I. 500#.

RECEIVED  
SEP 23 2002  
KCC WICHITA

9/23/02

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

1070

Signed Dennis J. Hamel  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-24-02  
INV. NO. 1003060543

SEP 17 2002


INDEX  
 1-9-17W  
 NW SW SW

MURFIN DRILLING & #3 HRABE 'A' 1-9-17W  
 R. A. COMEAU NW SW SW  
 Contr. COMPANY TOOLS \_\_\_\_\_; ROOKS \_\_\_\_\_ County

E 1999 KB Comm. 12/31/62 Comp. 2/21/63 IP PMP 45 BOPD, NW/LANS.  
 3297-3305; GR 39

SMP Tops	Depth	Datum
ANH	1275	+624
TOP	2875	-876
HEEB	3087	-1088
TOR	3109	-1110
LANS	3130	-1131
B/KC	3354	-1355
ARB	3426	-1427
NO MARM PICKED		
TD	3485	-1486

Casing  
 8" 202:  
 5" 3484:  
 DST 3156-3224/1 HR, 180' M, SCUM  
 OIL, BHP 650-580#, FP 0-60#:  
 COTD 3453: PERF 16/3434-38, A 500:  
 NO RESULTS: 20/3373-78 (MARM ZN)  
 A 1000, SWB 1 BOPH/3 HRS, 16/  
 3346-50, A 1000, SWB 2 1/2 BOPH/3  
 HRS, 12/3323-26, A 1000, SWB 2 1/2  
 BOPH/3 HRS, 32/3297-3305, A 3000  
 SWB 16 BOPH/8 HRS: CO 3369:



GEOL-BOB ARMSTRONG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS