

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01473-00-00 ⁶²
Spot: CSWSENV Sec/Twnshp/Rge: 1-9S-17W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: HRABE J Well Number: 1
County: ROOKS Total Vertical Depth: 3425 feet

Operator License No.: 8735 Conductor Pipe: Size _____ feet: \$111.31
Op Name: CRAWFORD, STEPHEN G. DBA S & M OI Surface Casing: Size 8.625 feet: 156 135 SX CMT
Address: 1725 250TH AVE. Production: Size 5.5 feet: 3424 150 SX CMT
HAYS, KS 67601 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2003 10:00 AM

Plug Co. License No.: 8735 Plug Co. Name: CRAWFORD, STEPHEN G. DBA S & M OIL

Proposal Rcvd. from: STEVE CRAWFORD Company: CRAWFORD, STEPHEN G. DBA S & M OIL Phone: (785) 650-4003

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Holes in casing.

Plugging Proposal Received By: DENNIS HAMEL

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 01/21/2003 12:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 1400'.
Mixed and pumped 120 sxs cement with 450# hulls.
POOH.
Tied onto 5 1/2" and pumped to pressure with 130 sxs cement with 50# hulls.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to annulus - instant pressure 1000#.

RECEIVED
JAN 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-24-03

INV. NO. 2003061109

JAN 21 2003