

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21479-00-00
Spot: E2SESWSW Sec/Twnshp/Rge: 1-9S-17W
330 feet from S Section Line, 1165 feet from W Section Line
Lease/Unit Name: HRABE A Well Number: 7
County: ROOKS Total Vertical Depth: 3490 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3489 150 SX CMT
Surface Casing Size: 8.625 feet: 199 180 SX CMT #113⁴³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2003 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
D.V. Tool at 1318' w/350 sxs.
F.L. 1475'. PBTD 3465'. Perfs 3167' - 3433'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/24/2003 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 185 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 700#. S.I.P. 600#.
Hooked up to backside - pumped 15 sxs cement with 100# hulls.
Max. P.S.I. 600#. S.I.P. 500#.

RECEIVED
JUL 30 2003
KCC WICHITA

7/30/03

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 7-30-03

INV. NO. 2004060274

Form CP-2/3

JUL 28 2003

MURFIN DRILLING CO
 617 UNION CENTER
 WICHITA, KS 67202
 CONTR COMPANY TOOLS

#7 HRABE "A"

1-9-17W
 330' FSL &
 1165' FWL, SW/4

CTY ROOKS

GEOL _____ FIELD WESTHUSIN

E 2001 KB CM 11/24/81 CARD ISSUED 8/5/82 IP P 36 BO & 79 BWPD
 1996 GL ARB 3431-3433
 API 15-163-21,479 LKC 3167-3350 OA

+	+	+
+	+	+
+	+	+

LOG TOPS	DEPTH	DATUM
ANH	1271	+ 730
B ANH	1303	+ 698
HEEB	3084	-1083
TOR	3113	-1112
LKC	3131	-1130
B KC	3376	-1375
ARB	3431	-1430
LTD&RTD	3490	-1489

8 5/8" 206/150sx; 4 1/2" 3489/575sx 2760 TOC

DST (1) 3438-3447 (ARB)/30-60-30-60,
 REC 90' MDY WTR W/FEW SPT OIL,
 SIP 1009-990#, FP 36-54/67-73#,
 HP 1727-1699#

MICT - CO, PF (ARB) 3431-33 w/8 SPF,
 AC 500G, SWB LD, TSTD, PF (LKC) 3341-
 50, 3315-19, 3291-95, 3234-38, 3186-
 88, 3167-72 w/4 SPF, AC 2000G, SWB LD
 TSTD, POP, P 36 BO & 79 BWPD, 2/1/82
 COMMINGLED

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS