

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-20087-00-00

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6791

OPERATOR: GEORGE P. CRAWFORD
NAME & ADDRESS: R.I. BOX 93
NATONIA, KANSAS
67651

FEET FROM N/S SECTION LINE _____
FEET FROM W/E SECTION LINE _____

LEASE NAME ^{W.H. KCC} HRABE WELL # 1

COUNTY ROCKS

WELL TOTAL DEPTH 3460 \$ 112.45 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 200

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR HALLIBURTON OIL WELL CNT. LICENSE NUMBER _____

ADDRESS 1100 EAST 8TH ST. HAYS, KANSAS 67601

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 2ND MONTH: SEPT YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM GEORGE P. CRAWFORD

(COMPANY NAME) GEORGE P. CRAWFORD OIL (PHONE) 913-885-4808

WERE: 8 5/8" - 200 FT S.P. CUC. 1 1/2^{SK} CNT., 5 1/2" SET @ 3459 FT. 1 1/2^{SK} CNT.

PLUG BACK T.D. 3410 FT, PERFS. 3400 FT TO 3410 FT

SQUEEZED FROM 1272 FT TO SURFACE (CUC.) 1 1/2^{SK} CNT.

NO PIPE RECOVERY, ORDER 160^{SK} 50/50 FOZ MIX 6% GEL 3% CH. CL.

19^{SK} GEL, 4^{SK} HULL'S, AND 5 1/2" PLUG, PUMPED IN WITH PUMP

TRUCK, ANNULUS + 5 1/2" CSG. PLUGGING PROPOSAL RECEIVED BY MARION SCHMIDT
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 2ND MONTH: SEPT. YEAR: 19 83

ACTUAL PLUGGING REPORT

ORDERED 160^{SK} 50/50 FOZ MIX 6% GEL 3% CH. CL., 19^{SK} GEL, 4^{SK} HULL'S, 8 5/8" PLUG.

CELLAR WAS DUG OUT. CEMENT DID CIRCULATE TO SURFACE,

IN ANNULUS BETWEEN 5 1/2" CSG. AND 8 5/8" S.P.

PUMPED IN 5 1/2" CSG. 10^{SK} CNT., 40^{SK} CNT. 1 1/2^{SK} HULL'S MIXED IN,

15^{SK} GEL, 1/2^{SK} HULL'S, 20^{SK} CNT., 4^{SK} GEL 1 1/2^{SK} HULL'S, RELEASED PLUG,

REMARKS: AND 50^{SK} CNT., MAX. PRESSURE 1500 PSE, SHUT IN @ 1200 PSE

CEMENTED BY HALLIBURTON CNT.

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1983

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

9/12/83
CONSERVATION DIVISION
Wichita, Kansas

SIGNED MARION SCHMIDT ✓
(TECHNICIAN) DOIC

INVOICED

DATE 9-27-83
INV. NO. 5522-W

2 FORM CP-2/3
REV. 6-83