

4-060876

4-26

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,927-00-00  
170'E.of  
N2 SE SE /4 SEC. 02, 09 S, 17 W  
990 feet from S section line  
490 feet from E section line

Operator license# 5134

Lease: Howat <sup>KCC ZAP</sup> ~~Howatt~~ Well # 3

Operator: Graham-Michaelis

County: Rooks

Address: P.O. Box 247  
Wichita, Kansas 67201

Well total depth 3447 <sup>112.02</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 243 feet

Aband. oil well X, Gas well       , Input well       , SWD       , D & A       

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 26 Month: April Year: 1996

Plugging proposal received from: Mike Kelso/Richard

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 220 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

RECEIVED  
KANSAS CORPORATION COMMISSION  
5/14/96  
MAY 14 1996

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[    ], Part[    ], None[ X ]

CONSERVATION DIVISION  
WICHITA, KS

Completed: Hour: 11:15 A.M., Day: 26, Month: April, Year: 1996

Actual plugging report: 8 5/8" to 243' w/175 sxs. 4 1/2" to 3443' with 100 sxs. Perfs from 3146' - 3326'. Sanded to 3100' and spotted 4 sxs cement with dump bailer. Shot casing loose at 1700' and was free. Mixed and pumped 80 sxs cement with 200# hulls. Pulled casing to 1300' and pumped 30 sxs cement with 200# hulls. Pulled casing to 750' and pumped 30 sxs cement with 100# hulls. Pulled casing to 200' and circulated cement to surface with 25 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing. Checked cement top 6' from surface 5-1-96 by Dennis Hamel.

Condition of casing(in hole): GOOD X BAD        Anhy.plug: YES X NO       

Bottom plug(in place): YES X, CALC       , NO        Dakota plug: YES X, NO       

Plugged through TUBING       , CASING X. Elevation: 2005 GL

I did    / did not X observe the plugging.

Herb Deines  
DH (agent)  
Form CP-2/3

INVOICED  
DATE 5-15-96  
INV. NO. 45598