

To: 6 040920
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-14

API NUMBER 15- 163-20,679 0000
NE NW NE, SEC. 4, T 9 S, R 17 W/E
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Co. Inc.
Name & Address 110 N. Market Suite 205
Wichita, Ks. 67202

Lease Name Twin Mounds Unit #11 ^C ^{KCC} ^{7AP} 8-5
County Rooks 113.75
Well Total Depth 3500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 236' w/140

Abandoned Oil Well _____ Gas Well _____ Input Well x SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: 8:30AM Day: 13 Month: July Year: 19 88

Plugging proposal received from Ed Mondero

(company name) Pickrell Drilling (phone) _____

were: 4 1/2" casing set at 3496' w/125 sks. Perf at 3441' - 3448'.

Ordered 150 sks 60/40 Poz 6% Gel w/3 sks Hulls, plus 150 sks 65/35 Poz 10% Gel w/3 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988 7/16/88

CONSERVATION DIVISION
Wichita, Kansas Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 14 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Plugged bottom of 4 1/2" casing as follows:

Pumped 150 sks 60/40 Poz 6% Gel plus 3 sks Hulls mixed in cement; followed with wiper plug to 1430'. Casing pressured up to 600#. Perf casing at 1325' at 825' on July 14, 1988.
Pumped 100 sks cement in casing w/300# Hulls mixed in cement. Max 400#. S.I. 200#. Pumped 50 sks in 8 5/8" S.P. Max 500# S.I. 400#.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 9-20-88
INV. NO. 22319

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis Hamel