

4-070052

7-15

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-22,633-0000

H.D. NW NE NW /4 SEC. 04, 09 S, 17 W
7-18-97 4950 feet from S section line
3630 feet from E section line

Operator license# 30742

Lease: Diehl Well # 1

Operator: Palomino Petroleum, Inc.

County: Rooks 114.69

Address: 4924 SE 84th Street
Newton, Kansas 67114

Well total depth 3529 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 260 feet
W/170 sxs.

Aband. oil well ☒, Gas well ☐, Input well ☐, SWD ☐, D & A ☐

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:30 A.M. Day: 15 Month: July Year: 1997

Plugging proposal received from: Kent Strube

Company: D.S. & W. Well Service Phone: 316-587-3361

Were: 4 1/2" casing set at 3529' with 125 sxs. Perfs at 3420' - 3425'.
Salt at 1674' - 1808'. Anhy at 1330'. Dakota at 492'. Cut 4 1/2" casing at 1825' - 1375' -
750' - 700' - 475' - 250'.
Ordered 150 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED
KANSAS CORP COM
1997 JUL 21 P 1:20
7/21/97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:30 P.M. Day: 15 Month: July Year: 1997

Actual plugging report: Plug bottom perfs with sand at 3370' with 4 sxs on top. Cut casing
at 1875' and 1325'. Allied (Russell, Kansas). Pumped 40 sxs at 1600#. S.I.P. 1000#. Cut
at 950' - no recovery. Cut at 750' and 700' - no recovery. Pumped 40 sxs 60/40 pozmix - 10%
gel with 100# hulls. Displaced 2 bbl. Cut at 475' - no recovery. Cut loose pipe at 250'.
Pulled one joint and pumped 70 sxs 60/40 pozmix - 10% gel with 400# hulls on vacuum.

Remarks:

Condition of casing(in hole): GOOD ☒ BAD ☐ Anhy plug: YES ☒ NO ☐Bottom plug(in place): YES ☒ CALC ☐ NO ☐ Dakota plug: YES ☒ NO ☐Plugged through TUBING ☐ CASING ☒ Elevation: 2017 GL

I did[X] / did not[] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED
JUL 22 1997

DATE

INV. NO.

48626

7-15