

6030609

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,802 *R*

NWSE SEC. 4, T. 9 S, R. 17 *ND*

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name DIEHL Well # 2

Operator: ENERGY THREE, INC.

County ROOKS 116.03

Name & Address P.O. Box 1505

Well Total Depth 3570 feet

GREAT BEND, KANSAS

Conductor Pipe: Size _____ feet

67530

Surface Casing: Size 8 5/8 feet 809

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BIG THREE DRUG CO. INC. License Number 5836

Address Box 52, GORHAM, KANSAS 67640

Company to plug at: Hour: PM Day: 18 Month: 11 Year: 19 85

Plugging proposal received from STAN LOVELADY

(company name) _____ (phone) _____

were: 8 5/8 SET @ 809' w/350sx. WITH NO LOSS OR GAIN OF FLUID AND HOLE FULL OF NO LESS THAN 36 UIS. MUD SPOT CEMENT PLUGS w/ DRILL PIPE. ORDER: 160sx. 60/40poz. 6% GEL 3% cell 8 5/8 w.p. B J TITAN CEMENT CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30PM Day: 18 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 1350' DISPLACE 25sx. CNT. MIX LAYDOWN D.P. TO 850' DISPLACE 100sx. CNT. MIX + 1sx. HULLS LAYDOWN D.P. PUSH W.P. TO KELLY DEPTH DUMP 1/2sx. HULLS AND 10sx. CNT. MIX. TO BASE OF CELLAR DISPLACE 15sx. CNT. MIX AND 10sx. CNT. MIX. IN RATHOLE AND MOUSEHOLE w/ JOINT OF PIPE. PLUG COMPLETE

Remarks: ELEV. 2017 ANHY 1321-1362
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE DEC 10 1985

DEC 9 1985

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 11358

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

42-6-85
mm