

4-070078

15-163-03205-00 00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 6-55

SW NW SW /4 SEC. 05, 09 S, 17 W  
1650 feet from S section line  
4950 feet from E section line

Operator license# 30606  
Operator: Murfin Drilling Company  
Address: 250 N. Water - #300  
Wichita, Kansas 67202

Lease: Thompson Well # 4  
County: Rooks 111.05

Well total depth 3417 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 214 feet  
W/175 sxs.

ABAND. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD. \_\_\_\_\_, D&A \_\_\_\_\_

Plugging contractor: Murfin Drilling License# 30606

Address: 250 N. Water - #300 - Wichita, Kansas 67202

Company to plug at: Hour: 10:30 A.M. Day: 13 Month: November Year: 1997

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Phone: 785-421-5572

Were: 5 1/2" casing set at 3407' w/125 sxs - top of fish 3002'.  
Perforated Dakota 866' - Anhy 1323' - Salt 1820'  
Ordered 325 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Perfs at 3124' - 3353' - Open hole 3407' - 3417'.

RECEIVED  
KANSAS CORP COM  
NOV 20 AM 11:11  
11/20/97

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part [ ], None [ ]

Completed: Hour: 12:30 P.M., Day: 13, Month: November, Year: 1997

Actual plugging report: Ran tubing to 2939'. Allied pumped 100 sxs 60/40 pozmix - 10% gel w/200# hulls in last 50 sxs. Pulled tubing to 1600'. Allied pumped 100 sxs with 200# hulls. Pulled tubing to 307' - pumped 40 sxs cement circulated PTOH and squeezed with 10 sxs. Max. P.S.I. 500#. S.I.P. 250#. Pumped 10 sxs down annulus with 100# hulls. Max. P.S.I. 400#. S.I.P. 200#.

Remarks:  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD  Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 1991 GL

I did  / did not [ ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

NOV 24 1997

DATE

INV. NO. 49568