

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19024-00-00
Spot: SWNESW Sec/Twnshp/Rge: 5-9S-17W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: JH THOMPSON Well Number: 2
County: ROOKS Total Vertical Depth: 3435 feet

Operator License No.: 6033
Op Name: MURFIN DRILLING CO.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/11.64
Surface Casing: Size 8.625 feet: 208 175 SX CMT
Production: Size 5.5 feet: 3425 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/21/2002 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs and bridge plugs set: 3133' - 3382'
Squeeze 956' - 760' w/350 sxs.
Arb. Open hole 3425' - 3435'.
Packer stuck in the hole at 3106'.

Plugging Proposal Received By: PAT STAAB Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/21/2002 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perforated at 1340' - 1800'.
RIH with tubing to 2013' and pumped 25 sxs 60/40 pozmix neat and 75 sxs 60/40 pozmix with 300# hulls.
Pulled tubing to 1050' and pumped 95 sxs with 200# hulls to circulate cement to surface.
Tied onto backside and pressured to 500#.
Pulled tubing and tied onto casing with a swedge and pumped 130 sxs 60/40 pozmix.
Max. P.S.I. 800#. S.I.P. 350#.
Job complete.

RECEIVED

MAY 23 2002

KCC WICHITA


S/23/02

Remarks: ALLIED CEMENTING COMPANY - TICKET #10671.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-24-02

INV. NO. 2002061838

MAY 22 2002

MAICEA

SUNRAY OIL #2 THOMPSON 5-9-17W SW NE SW
 Contr. STICKLE DRLG ROOKS County
 E 201 3RB Comm. Comp. 5-20-55 IP 100 BOPD

Tops	Depth	Datum
HEEB	3115	-1102
LANS	3156	-1113
ARB	3123	-1110
TD	3135	-1122

Casing
 8" 208
 5" 3125
 DST 3242-62/1 HR, 15' MUD,
 15' H OCM, BHP 800#
 DST 3312-26/1 HR, 30' SL
 OCM, BHP 390#
 CO TD: 1 GOPH: DD 3135: 5
 GOPH: ACID 750: 15 BO/3 HR:
 ACID 1000: SWB 15 BO/3 HR:
 DOPITA SE POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS