

4-070139

3-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-23,218-0000

NW NE SE /4 SEC. 05, 09 S, 17 W
2310 feet from S section line
990 feet from E section line

Operator license# 30730
Operator: Horizontal Development
And Production
Address: 23077 Pedernales Canyon
Spicewood, Texas 78669

Lease: Fischer Well # 1
County: Rooks 112.42
Well total depth 3459 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 210 feet
W/135 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Quality Well Service License# 31925

Address: 249 E. Beth Dr. - Sterling, Kansas 67579

Company to plug at: Hour: 2:00 P.M. Day: 24 Month: March Year: 1999

Plugging proposal received from: Mike Sternberg

Company: Horizontal Development & Production Phone: 512-264-3011

Were: 5 1/2" casing set at 3451' w/135 sxs.
Perfs: 3206' - 3269'. Cast iron plug at 3315'.
Cemented 1356' to surface
Wireline TD 3308'. Fluid 210' from surface.
Ordered out 240 sxs 60/40 pozmix - 10% gel - 16 sxs gel and 500# hulls.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All , Part , None

Completed: Hour: 2:00 P.M. Day: 24, Month: March, Year: 1999

Actual plugging report: Allied pumped 75 sxs 60/40 pozmix - 10% gel with 200# hulls, followed with 16 sxs gel spacer with 200# hulls, followed with 120 sxs cement with 100# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Backside pressured up to 600#.

RECEIVED

STATE CORPORATION COMMISSION

MAR 30 1999 3/30/99

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: 2011 GL

I did / did not observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE 4-2-99

INV. NO. 60767