

6040453

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-01488-0000

SENESE, SEC. 6, T. 9 S, R. 17 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5354

Operator: Beren Corp
Name & Address: 910 Fourth Fin Ct
Wichita, KS 67202

_____ feet from S section line

_____ feet from E section line

Lease Name Moos Well # 4

County Rooks 111.28

Well Total Depth 3424 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 109 w/100 ac

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Hays, Kansas

Company to plug at: Hour: 12:30 PM Day: 19 Month: 9 Year: 19 85

Plugging proposal received from George Jergenson

(company name) Okmar (phone) _____

were: 5 1/2" set @ 3407 w/100 sx open hole comp.

Sq @ 700' w/200 sx.

Ordered 225 sx 6940 poz 10% gel, 22 sx gel,

8 sx hulls & 5 1/2" w. plug.

Witnessed by M. Schmidt

Plugging Proposal Received by Dennis J. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50 PM Day: 17 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT

Impd in 5 1/2" csg -> 25 sx emt w/1 sx hulls, ->

22 sx gel w/2 sx hulls, -> Rel. W. plug -> 100 sx

emt w/2 sx hulls Shut-in press 300"

Hooked-up to 8 5/8" S.P. pased in 100 sx emt w/

3 sx hulls S.I.P. 200"

Remarks: Return 9-19-85 to check emt - O.K.

(If additional description is necessary, use BACK of this form.)

NOTICED (If did not observe this plugging.)

STATE CORPORATION COMMISSION

DATE OCT 03 1985

Signed Dennis J. Hamel
(TECHNICIAN)

INV. NO. 10310

SEP 30 1985

9/20/85

33
9-27-85
my