

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

047 ka ab

API # 15 - ~~15~~-21,298-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date \_\_\_\_\_

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056  
(Owner / Company Name) (Operator's)

Address: 9431 E. Central, Suite 100 City: Wchita

State: Kansas Zip Code: 67206 Contact Phone: ( 316 ) 684 - 8481, Ext. 216

Lease: CROSS Well #: 2-19 Sec. 19 Twp. 24S S. R. 17  East  West

NW - SE - NE - NE Spot Location / QQQQ County: Edwards

4455 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

495 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 307'KB Cemented with: 225sx Sacks

Production Casing Size: 4-1/2" Set at: 4558' Cemented with: 200sx Sacks

List (ALL) Perforations and Bridgeplug Sets: 4403'-4408', 4402'-4408', 4420'-4426', tagged sand @ 4510'

Elevation: 2130'KB ( G.L. /  K.B.) T.D.: 4560' PBDT: 4510' Anhydrite Depth: 1172'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Heavy mud, hulls, cement and plug according to KCC regulations.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mr. Rob Long

Phone: ( 620 ) 793 - 0915

Address: 709 E. Santa Fe. City / State: Ellinwood, KS. 67530

Plugging Contractor: Quality Well Service KCC License #: 31925

Address: 401 West Main, Lyson, KS. 67554 Phone: ( 620 ) 727 - 3410

Proposed Date and Hour of Plugging (if known?): Unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: August 24, 2007 Authorized Operator / Agent: \_\_\_\_\_

*Lauren M Page*  
Lauren M Page  
(Signature)

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 27 2007

CONSERVATION DIVISION  
WICHITA, KS

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CROSS #2-19

Located: NW SE NE NE, Section 19-24S-17W, Edwards County,  
Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 29, 1987

COMPLETED: November 4, 1987

TOTAL DEPTH: 4560'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 90 Surface Soils, Sand	Ran 7 joints new 8 5/8" new casing. 295.22' pipe set at 307' K.B.
90 - 310 Clay, Shale	Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 11:30 AM, 10-29-87, by Halliburton.
210 - 1172 Shale	
1172 - 1184 Anhydrite	
1184 - 1875 Shale	
1875 - 4560 Lime and Shale	Ran 111 joints 4 1/2", 50# casing. 4549.59' pipe set at 4558' K.B. Cemented with 100 sacks Lite and 100 sacks 50/50 Pozmix, plus F. G. Holl mix. Plug down at 6:45 AM, 11-4-87, by Halliburton.

Deviation Surveys: 1/4° at 2205'  
1 3/4° at 4410'

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 27 2007

CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

August 29, 2007

Re: CROSS #2-19  
API 15-047-21298-00-00  
19-24S-17W, 4455 FSL 495 FEL  
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after February 25, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond

Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888