

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-22,511-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F & M OIL CO., INC. OPERATORS LICENSE NO. 5313

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE # (316) 262-2636

LEASE (FARM) Andreson "C" WELL NO. 1 WELL LOCATION NE NW NW COUNTY Rooks

SEC. 17 TWP. 9S RGE. 17W ~~(S)~~ or (W) TOTAL DEPTH 3610' PLUG BACK TD -----

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 222' CEMENTED WITH 160 SACKS

CASING SIZE ----- SET AT ----- CEMENTED WITH ----- SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 1st plug @ 3510' w/20 sxs, set 2nd
plug @ 1400' w/20 sxs, set 3rd plug @ 775' w/100 sxs & 1 sx Celo-flakes, set 4th plug @ 260' w/
40 sxs, set 5th plug @ 40' w/10 sxs, 10 sxs in rat hole, cmt by Sun w/ 50/50 poz., 6% gel, 3% CC

(If additional space is needed use back of form) plug down @ 7:45 PM
11/23/84

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN November 23, 1984 7:45 PM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS RECEIVED
STATE CORPORATION COMMISSION

Lyle Cason PHONE # (316) 596-2140

ADDRESS Rt. 2, Langdon, Kansas 67549

PLUGGING CONTRACTOR Union Drilling Co., Inc. LICENSE NO. 5103

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE # (316) 262-1872

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: X [Signature]
(Operator or Agent)

DATE: December 10, 1984

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 10 4 84
month day year

API Number 15- 163-22,511-00-00

OPERATOR: License # 5313
Name F. & M OIL CO., INC.
Address 422 Union Center
City/State/Zip Wichita, Kansas 67202
Contact Person R. D. Messinger
Phone (316) 262-2636

NE NW NW
(location) Sec 17 Twp 9 S. Rge 17W East West

4950' Ft North from Southeast Corner of Section
4290' Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5103
Name Union Drilling Co., Inc.
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet
County Rooks

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Lease Name Andreson "C" Well # 1

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator N/A
Well Name
Comp Date

Depth to Bottom of fresh water 100 feet

Lowest usable water formation Dakota

Depth to Bottom of usable water 800 feet

Surface pipe by Alternate: 1 2

Surface pipe to be set 220' feet

Conductor pipe if any required

Ground surface elevation

This Authorization Expires 4-2-85

Approved By 10-2-84 R

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plug the hole to K.C.C. specifications.

Date 10-2-84 Signature of Operator or Agent

[Handwritten Signature]
Title Vice-President

RECEIVED
INFORMATION COMMISSION
DEC 03 1984
CONSERVATION DIVISION
Wichita, Kansas