

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

**WELL PLUGGING APPLICATION FORM**

(File One Copy)

15-163-0139-00-01

API NUMBER Drld. in 1937 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR ARCO Oil and Gas Company OPERATORS LICENSE NO. 5398

ADDRESS P.O. Box 3708, Enid, Oklahoma 73702 PHONE # (405) 233-6800

LEASE (FARM) Robert J. McClay WELL NO. 2 WELL LOCATION SW/4 COUNTY Rooks

SEC. 12 TWP. 9S RGE. 17W (E) or (W) (W) TOTAL DEPTH 3333' PLUG BACK TD 3333'

Check One:

OIL WELL X GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 10 3/4" SET AT 105' CEMENTED WITH 130 SACKS

CASING SIZE 7" SET AT 3154' CEMENTED WITH 125 SACKS

PERFORATED AT 5 1/2" liner. Top @ 3115', Btm @ 3312 3139'-3309'

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK X JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot cmt over perforations. Spot cmt from TOC to cover, csg leak @ 1128. Spot cmt from TOC to surface. Pump cmt down 7"x5 1/2" annulus. Cut off 103/4"-7"-5 1/2". Weld on plate w/ 2" collar. Pmp down 7"x10 3/4" annulus.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? \_\_\_\_\_  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8-29-85 @ 9:00 A.M. Contacted Kans. Corp. Comm. for verbal approval to start plugging..

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 9/12/85

Robert L. McGlinn

PHONE # (316) 793-5467 RECEIVED  
STATE CORPORATION COMMISSION

ADDRESS Box 849, Great Bend, Kansas 67530

PLUGGING CONTRACTOR Ostrom Well Service, Inc.

LICENSE NO. 5680 SEP 17 1985  
CONSERVATION DIVISION  
Wichita, Kansas

ADDRESS 1012 W. Mill, Plainville, Kansas

PHONE # (913) 434-2707

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Robert L. McGlinn  
(Operator or Agent)

DATE: 9/13/85