

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21956-00-01
Spot: E2SESE Sec/Twnshp/Rge: 15-29S-11W
660 feet from S Section Line, 100 feet from E Section Line
Lease Name: HISKETT C Well #: 1-15
County: PRATT Total Vertical Depth: 4760 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4756	2480	WITH 175 SX CMT
SURF	8.625	256		WITH 200 SX CMT <u>154,70</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/14/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 05/14/2008 11:15 AM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 100# HULLS & 25 SX CMT TO 3300'. PUMPED PLUGS THROUGH CASING WHILE PUMPING. 1ST PLUG AT 660' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4650	4654		SIMPSON SAND
4314	4322		MISSISSIPPI CHER
3760	3766		DOUGLAS SAND

INVOICED

DATE 7-1-08
INV. NO. 2009060001

RECEIVED
KANSAS CORPORATION COMMISSION


JUN 06 2008

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-208

PLG