

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21828-00-00  
Spot: E2NWNWNE Sec/Twnshp/Rge: 21-21S-11W  
330 feet from N Section Line, 2200 feet from E Section Line  
Lease Name: SMITH ESTATE B Well #: 4-21  
County: STAFFORD Total Vertical Depth: 3480 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		725		WITH 2 SX CMT
CIBP		3350		WITH 4 SX CMT. 113.10
PROD 4.5		3479	0	WITH 150 SX CMT
SURF 8.625		305		WITH 235 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2008 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 06/05/2008 12:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

CIBP @ 3350' & 4 SX CMT. 1ST PLUG SET CIBP @ 725' & 2 SX CMT. TEST CASING TO 400#. 2ND PLUG PERFORATE AT 690'. PUMP 90 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 1200#. 3RD PLUG PUMP 110 SX CMT DOWN 8 5/8" CASING. MAXIMUM PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
3408	3412		

**INVOICED**  
DATE 7-1-08  
INV. NO. 2009060001


RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 13 2008

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KS

District: 01



Signed

*[Signature]*  
(TECHNICIAN)

*[Handwritten mark]*