

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20428-00-00
Spot: SESWNW Sec/Twnshp/Rge: 10-14S-17W
2983 feet from S Section Line, 4318 feet from E Section Line
Lease Name: SANDER Well #: 1
County: ELLIS Total Vertical Depth: 3555 feet

Operator License No.: 8507
Op Name: PAXCO, INC.
Address: 8920 PEPPERTREE CIR
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3548	0	w/75 sxs cmt
SURF	8.625	225	0	w/150 sxs cmt <u>115.54</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2008 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM Company: PAXCO, INC. Phone: (316) 634-1714

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 3 sxs cc - 500# hulls.
Dig out 8 5/8" - found cement to the top.
This well had several squeezes from the anhydrite to the surface.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2008 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3226' - pumped 100 sxs cement with 3 sxs calcium - let set one hour - had little returns.
Pulled tubing to 1666' - pumped 105 sxs cement - good circulation of cement.
Pulled tubing out - filled 4 1/2" down the top with 15 sxs cement - tube full.

INVOICED
DATE 7-3-08
INV. NO. 2009060024

Remarks: ALLIED CEMENTING COMPANY-TICKET #30231.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 11 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Marvin Mills
(TECHNICIAN) *cm*

Form CP-2/3

JUN 09 2008

PM

