

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24730-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 11-20S-11W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: PANNING Well #: 3  
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 32325  
Op Name: POPP OPERATING, INC.  
Address: 191 NE 150 RD PO BOX 187  
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3377	0	w/170 sxs cmt
SURF	8.625	507	0	w/435 sxs cmt

109.85

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2008 10:30 AM  
Plug Co. License No.: 31925 ~~99977~~ Plug Co. Name: QUALITY OIL WELL CEMENTING Service, Inc.  
Proposal Rcvd. from: \_\_\_\_\_ Company: POPP OPERATING, INC. Phone: (620) 653-2737

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 06/09/2008 1:00 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Perfs:

Sanded to 3270' and dumped 5 sxs cement.  
Cut off casing at 2280'.  
Pulled to 1450' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled to 500' - pumped 40 sxs cement with 100# hulls.  
Pulled to 150' - circulated with 75 sxs cement.

INVOICED

DATE 7-3-08  
INV. NO. 2009060028

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 11 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed Case Morris  
(TECHNICIAN)

Form CP-2/3

JUN 09 2008

replacement card

POPP OPERATING  
HOISINGTON KS 67544

11-20S-11W  
SW NW SW

#3 PANNING

site 1-1/2 S & 2-1/4 E OF ELLINWOOD KS  
contr: DISCOVERY DRILLING #2  
opd: ROBERT STOLZLE  
date 01/14/2002

city: BARTON  
field: CHASE-SILICA  
AP# 15-009-24730


if: ROBERT STOLZLE  
date 01/14/2002  
date 01/22/2002  
date 01/27/2002  
date 05/27/2002  
date 08/18/2003

ELV: 1764 KB, 1756 GL LOG

tops	depth/datum
SC	495 +1269
GRDHAVEN	2220 -456
STOT	2308 -544
TARK LM	2365 -601
HOW	2517 -753
TOP	2619 -855
PLATTSM	2785 -1021
HEEB	2878 -1114
DOUG SH	2910 -1146
LANS	3023 -1259
LANS E	3094 -1330
LANS G	3105 -1341
LANS J	3188 -1424

IP status  
OIL, P 18 BO & 960 BWPD, ARB 3277-3279, 03/04/2002  
BKC .....3256 -1492  
ARB .....3276 -1512  
PBTD .....3310 -1546  
LTD .....3379 -1615  
RTD .....3380 -1616  
INFO RELEASED: 8/18/2003 - WAS OIL WELL - TIGHT HOLE  
CSG: 8-5/8" 506.77 / 435 SX (ALT 1), 5-1/2" 3377 / 170 SX  
COMMENT: MI & RJRT 1/22/2002  
SHOWS: 2830-2834 (SHAW LM, TR V PR PORO, OIL STN,  
FR-WK CUT & FLUOR), 3043-3048 (LANS LM, FNPT PORO,  
SME GD PORO, LT STN, GD CUT & FLUOR), 3062-3068  
(LANS LM, FR-PR PORO, LT STN, GD CUT & FLUOR, ?  
PERM), 3080-3084 (LANS LM, PR PORO, GD STN, GD CUT &  
FLUOR, ? PERM).

COPYRIGHT 2003  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)