

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-00560-00-01

Spot: ^{SW}SWNESW

Sec/Twnshp/Rge: 25-4S-27W

1605 1650 feet from S Section Line, 383 3630 feet from E Section Line

Lease Name: JENNINGS UNIT

Well #: 4-2

County: DECATUR

Total Vertical Depth: 3543 feet

Operator License No.: 31100

Op Name: ROBUCK, BRETT DBA ROBUCK PETRO

Address: PO BOX 345

MCCOOK, NE 69001

String Size Depth (ft) Pulled (ft) Comments

PROD 7 3532 0 w/175 sxs cmt

SURF 10.75 680 0 w/400 sxs cmt

115.15

Well Type: EOR

UIC Docket No: E08190.3

Date/Time to Plug: 06/11/2008 9:00 AM

Plug Co. License No.: 31660

Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY

Proposal Rcvd. from: BRETT ROBUCK

Company: ROBUCK PETROLEUM COMPANY Phone: (308) 345-7200

Proposed Plugging Method:

Ordered 600 sxs 60/40 pozmix - 4% gel - 7 sxs gel - 2 sxs cc. - 500# hulls.
CIPB 3150'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/11/2008 1:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Log Tech perforated 2000' and 1300'.
Ran 2 3/8" tubing to 2880'. S.O.S. pumped 7 sxs gel spacer, followed with 100 sxs 60/40 pozmix - 4% gel with 3% cc and 200# hulls.
Pulled tubing to 2008' - pumped 350 sxs cement with 200# hulls - circulated cement.
PTOH. Topped off with 30 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.
Hooked up to backside - instant 400#.

Perfs:

Top	Bot	Thru	Comments
3050	3143		

INVOICED
DATE 7-3-08
INV. NO. 2009060035

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: SOS CEMENTING COMPANY.

Plugged through: TBG

JUN 13 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

PPT

JUN 12 2008

25-4-27M
SW NE SW

#2 JENINGS

TEXAS COMPANY

Contr. STICKLE DRILLING COMPANY DECATUR County

E. 2523 RB Comm. 1-16-53 IP 150 BOPD

Tops	Depth	Datum
ANH	2020	503
BURL	3139	- 616
HOW	3187	- 664
TOP	3251	- 728
HEEB	3381	- 858
LANS	3423	- 900
TD	3543	-1020

Casing
10" 680
7" 3532

DP, CO, 1 G OILY MPH
DD 3535, NO INC;
DD 3543, NO INC
ACID 500, SWB 3 1/2 BO &
1/2 BWPH/8 HRS

JENNINGS POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS