

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19117-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 17-22S-4E
4972 feet from S Section Line, 2397 feet from E Section Line
Lease Name: SPEIR Well #: 1
County: MARION Total Vertical Depth: 2975 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2821		700 SX
SURF	8.625	131		

96-69

Well Type: SWD UIC Docket No: D09700.0 Date/Time to Plug: 05/20/2008 9:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P. BANDY Company: TE-PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: PUMP 50@ 2460', CIRCULATE TO SURFACE FROM 250'.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2008 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

RAN TUBING TO 2356' AND PUMPED 50 SXS W/50# POLYFLAKE. PULLED TUBING TO 250' AND PUMPED 80' SXS CEMENT BEFORE LOSING CIRCULATION. WAITED 2 HRS AND PUMPED 50 SXS AND LOST CIRCULATION. WAITED 2 HRS AND PUMPED 50 SXS AND LOST CIRCULATION. WAITED 2 HRS AND PUMPED 50 SXS WAITED AN HOUR AND PUMPED 5 SXS TO CIRCULATE TO SURFACE. 5/21 WELL HEAD CUT OFF AND ANNULUS NOT CEMENTED 3:35. 5/23 CONSOLIDATED PUMPED 108 SXS CEMENT THROUGH 150' OF 1" TUBING TO CIRCULATE CEMENT TO SURFACE ON THE BACKSIDE OF THE CASING.

Perfs:

Top	Bot	Thru	Comments
2821	2925		

INVOICED
DATE 7-3-08
INV. NO. 2009060039
RECEIVED
KANSAS CORPORATION COMMISSION
JUN 19 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED WELL SERVICE TICKET #17540 TOTAL = 285 SXS, 60/40 POZ 4% GEL. CONSOLIDATED TICKET #13731 TOTAL = 108 SXS 60/40 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)