

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21232-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 6-33S-5W
356 feet from S Section Line, 1920 feet from E Section Line
Lease Name: SALSER DC Well #: 1
County: HARPER Total Vertical Depth: 4853 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4554	2350	
SURF	8.625	211		

157.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2008 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 682-1537

Proposed Plugging Method: TUBING PARTED, 3283', CASING PARTED 3280'. TPC 3540', PBTD 4479', 50 SKS CMT 3280', REC CASING, 35 SKS 950, 35 SKS 700, CIRC CMT 250-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2008 5:21 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TUBING WAS RUN INTO THE 4.5 CASING TO 3250', WHERE 50 SKS OF CEMENT WAS SPOTTED. THE CASING WAS SHOT AT 2391', AND 2350' WHERE THE CASING WAS RECOVERED. THE CASING WAS PULLED TO 950', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250', WHERE CMT WAS CIRCULATED TO SURFACE.

Perfs:

INVOICED
DATE 7-3-08
INV. NO. 2009060040

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 19 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED OIL WELL SERVICES 40/60 4% GEL

Plugged through: CSG

District: 02

Signed _____
(TECHNICIAN)