

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20260-00-00
Spot: E2SESESW Sec/Twnshp/Rge: 23-12S-12E
384 feet from S Section Line, 2873 feet from E Section Line
Lease Name: SS FARMS Well #: 14-23
County: WABAUNSEE Total Vertical Depth: 2339 feet

Operator License No.: 33116
Op Name: BERRY PETROLEUM COMPANY
Address: 1999 BROADWAY ST, STE 3700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2339		175 SX
SURF	8.625	355		185 SX

76.02

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2007 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RICK STEVENS Company: BERRY PETROLEUM COMPANY Phone: (972) 381-2701

Proposed Plugging Method: BOTTOM PLUG: 2026-2162, MIDDLE PLUG: PERF & Squeeze 883-1410, TOP PLUG: 0-350

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL
Date/Time Plugging Completed: 06/07/2007 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 2 7/8" TUBING TO 2162' AND PUMPED 25 SACKS OF CEMENT. PULLED TUBING UP TO 1450' AND PUMPED 15 SACKS OF CEMENT. PERFORATED THE 5 1/2" CASING AT 350' AND CIRCULATED 80 SACKS OF CEMENT TO SURFACE THROUGH PERFORATIONS.

Perfs:

Top	Bot	Thru	Comments
2154	2162		
2135	2138		
2120	2126		
2102	2104		
2076	2078		

RECEIVED
KCC DISTRICT #3

JUN 5 2008 TH

CHANUTE, KS

INVOICED
DATE 7-10-08
INV. NO. 2009060052

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Horner

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PKT