

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-197-20261-00-00  
Spot: E2SESENW Sec/Twnshp/Rge: 23-12S-12E  
2971 feet from S Section Line, 2734 feet from E Section Line  
Lease Name: SS FARMS Well #: 6-23  
County: WABAUNSEE Total Vertical Depth: 2403 feet

Operator License No.: 33116  
Op Name: BERRY PETROLEUM COMPANY  
Address: 1999 BROADWAY ST, STE 3700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2402		175 SX
SURF	8.625	355		214 SX

78.10

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/07/2007 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: RICK STEVENS Company: BERRY PETROLEUM Phone: (972) 381-2701

Proposed Plugging Method: BOTTOM PLUG: 2080-2360, MIDDLE PLUG: PERF. & SQUEEZE 940-1270, TOP PLUG 0-350.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/07/2007 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 2, 7/8" TUBING TO 2221' AND PUMPED 25 SACKS OF CEMENT. PULLED THE TUBING UP TO 1431' AND PUMPED 15 SACKS OF CEMENT. PERFORATED THE 5 1/2" CASING AT 350' AND CIRCULATED 80 SACKS OF CEMENT THROUGH THE PERFORATIONS.

Perfs:

Top	Bot	Thru	Comments
2214	2221		
2194	2197		
2177	2184		
2160	2162		
2134	2136		
2130	2132		

RECEIVED  
KCC DISTRICT #3

JUN 5 2008 TH  
CHANUTE, KS

INVOICED  
DATE 7-10-08  
INV. NO. 2009060052

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 26 2008

CONSERVATION DIVISION  
WICHITA KS

Form CP-2/3

PKT