

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19497-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 32-33S-12E
891 feet from S Section Line, 4785 feet from E Section Line
Lease Name: ALFORD Well #: 34
County: CHAUTAUQUA Total Vertical Depth: 1111 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	901		

36.11

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2007 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC Phone: (620) 725-5538

Proposed Plugging Method: GEL HOLE, 25 SACKS AT TD, 20 SACKS AT 700', 350' TO SURFACE.

Plugging Proposal Received By: RON ROWE Witness Type: NONE
Date/Time Plugging Completed: 11/15/2007 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

PULLED TUBING AND PACKER OUT OF 6.625 CASING. RAN 1" TO 980' AND GELLED WITH 20 BBLs OF GEL WATER. SPOTTED 25 SACKS OF CEMENT AND PULLED 1" OUT AND PERFORATED CASING AT 350'. RAN 1" BACK IN AND CEMENTED CASING INSIDE AND OUT WITH 125 SACKS OF CEMENT.

Perfs:

INVOICED
DATE 7-10-08
INV. NO. 2009060055

Remarks:

Plugged through:

District: 03

Signed Duane A Sims
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PCT