

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-19500-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 5-34S-12E  
3894 feet from S Section Line, 4026 feet from E Section Line  
Lease Name: AMERICAN PETROLEUM Well #: 26  
County: CHAUTAUQUA Total Vertical Depth: 1104 feet

Operator License No.: 5970  
Op Name: ELMORE, JOHN A. OR PATRICIA R.  
Address: 776 HWY 99  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	903		

35-88

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2008 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC. Phone: (620) 725-5744

Proposed Plugging Method: GEL HOLE, 25 SACKS AT TD, 20 SACKS AT 700', 350' TO SURFACE.

Plugging Proposal Received By: RON ROWE Witness Type: NONE  
Date/Time Plugging Completed: 01/14/2008 5:00 PM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

RAN 1" TO 1040' AND PUT 20 BBL. OF GEL WATER. SPOTTED 25 SACKS OF CEMENT, PULLED 1" UP TO 700' AND SPOTTED WITH 20 SACKS OF CEMENT. PULLED 1" OUT THEN STRETCHED CASING AND PARTED PIPE 10' DOWN. PERFORATED CASING AT 350'. RAN 1" BACK INTO CASING TO 350' AND CEMENTED TO SURFACE WITH 102 SACKS OF CEMENT.

RECEIVED  
KCC DISTRICT #3

JUN 23 2008

CHANUTE, KS

Perfs:

INVOICED

DATE 7-10-08  
INV. NO. 2009060055

Remarks:

Plugged through:

District: 03

Signed

Duane A. Sims  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 26 2008

CONSERVATION DIVISION  
WICHITA, KS

PKT