

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20659-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 11-33S-34W
2044 feet from S Section Line, 4852 feet from E Section Line
Lease Name: HITCH UNIT Well #: 5-1
County: SEWARD Total Vertical Depth: 6380 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	6379	3105	WITH 210 SX CMT
SURF	8.625	1627		WITH 650 SX CMT

207.35

Well Type: EOR UIC Docket No: E26115.7 Date/Time to Plug: 06/18/2008 8:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200-300# HULLS & 25 SX CMT. PLUG AT 1660' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2008 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:
PUMP 25 SX CMT & 300# HULLS @ 6122'. 1ST PLUG AT 1660' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6122	6240		

INVOICED

DATE 7-14-08
INV. NO. 2009060073

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 27 2008

Remarks: USED COMMON CEMENT BY SARGENTS.
Plugged through: CSG

District: 01 Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED

JUN 24 2008

KCC Dodge City