

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23718-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 2-10S-18W
600 feet from S Section Line, 450 feet from W Section Line
Lease Name: VANDOREN TRUST Well #: 2-2
County: ROOKS Total Vertical Depth: 3755 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	214		150 SX

122-04

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/15/2008 10:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 06/15/2008 11:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3700' w/25 sxs.
2nd. Plug at 1520' w/25 sxs.
3rd. Plug at 920' w/100 sxs.
4th. Plug at 265' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 7-14-08
INV. NO. 2009060075

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce D Basye
(TECHNICIAN)

CM

Form CP-2/3

JUN 27 2008

PT