

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00239-00-00

Spot: ^{SW} SWNESW

Sec/Twnshp/Rge: 12-13S-21W

KCC Per
GPS Pkt

1650 feet from S Section Line, 1650 Feet from W Section Line

Lease Name: EGGER

3885 Well #: 1

County: TREGO

Total Vertical Depth: 3828 feet

Operator License No.: 30717

Op Name: DOWNING-NELSON OIL CO INC

Address: PO BOX 372

HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3822	0	200 SX
SURF	8.625	197	0	150 SX

124.41

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/25/2008 10:30 AM

Plug Co. License No.: 99977

Plug Co. Name: QUALITY OIL WELL CEMENTING

Proposal Rcvd. from: TERRY W. PIESKER

Company: DOWNING-NELSON OIL CO., INC.

Phone: (785) 735-4363

Proposed
Plugging
Method:

Ordered 300 sxs 60/40 pozmix - 4% gel - 15 sxs gel - 600# hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/25/2008 11:30 AM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 100 sxs cement with 400# hulls - pumped 15 sxs gel.
Pumped 165 sxs cement with Max. P.S.I. 400#. Shut in.
Tied onto backside - full of cement.

Perfs:

Top	Bot	Thru	Comments
3822	3828		
3644	3650		
3626	3632		
3604	3611		
3522	3529		
3481	3486		
3447	3457		
3206	3216		

INVOICED

DATE 7-14-08

INV. NO. 2009060076

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3437.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

JUN 26 2008

PKS

BIRMINGHAM-BARTLETT DRIG #1 EGGER 12-13-21W
 SW NE SW

Contr. BIRMINGHAM-BARTLETT TREGO County

E 2152RB Comm. Comp. 11-14-58 IP 149 BOPD/ARB

Tops	Depth	Datum
ANH	1509	643
HEEB	3409	-1257
TOR	3428	-1276
LANS	3447	-1295
MARM	3717	-1595
ARB	3821	-1769
ID	3828	-1676

Casing
 8" 197
 5" 3822
 DST 3203-27/15", 20' M, BHP 1180#
 DST 3448-53/1 HR, 1605' G, 165' o, TR M,
 NW, BHP 1218#
 DST 3480-95/36", G/9", o/25", BHP 1280#
 DST 3499-3510/15", 8' MUD, BHP 1080#
 DST 3507-36/1 HR, 310' H OCM, 250' SL OCM,
 60' W, BHP 1300#
 DST 3574-93/30", 14' MUD, BHP 0#
 DST 3606-40/1 HR, 60' G, 550' V HO & GC
 WTR, BHP 1300#
 DST 3760-82/1 HR, 360' G, 590' o, BHP 1100#

DD 3828: 5 1/2 BOPH, NW

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS