

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00915-00-00  
Spot: <sup>NW</sup> NWSESW Sec/Twnshp/Rge: 12-13S-21W  
<sup>1043</sup> 990 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: EGGER 3820 Well #: 2  
County: TREGO Total Vertical Depth: 3828 feet

*KCC PKT per  
CORS*

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3817	0	200 SX
SURF	8.625	188	0	140 SX

*124.41*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2008 8:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: TERRY W. PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 15 sxs gel - 600# hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/25/2008 10:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 100 sxs cement with 400# hulls - pumped 15 sxs gel.  
Pumped 200 sxs cement with 200# hulls - hole on strong vacuum - set for 30 minutes.  
Pumped 30 sxs cement with Max. P.S.I. 300#. Shut in.  
Tied onto backside - pressured to Max. P.S.I. 400#. Full.

Perfs:

Top	Bot	Thru	Comments
3818	3828		
3766	3770		
3670	3672		
3626	3630		
3603	3608		
3581	3590		
3519	3522		
3478	3482		
3204	3214		

**INVOICED**

DATE 7-14-08

INV. NO. 2009060074

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 02 2008


CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #2436.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

CM

*PKT*

BIRMINGHAM-BARTLETT

#2 EGGER

12-13-21W

NW SE 8W

Contr. BIRMINGHAM-BARTLETT

TREGO County

E. 2154 RB Comm. Comp. 12-26-58

IP 182 BOPD

Tops	Depth	Datum
ANH	1507	647
HEFB	3406	-1252
TOR	3426	-1272
LANS	3444	-1290
MARM	3748	-1594
CONG	3785	-1631
ARB	3814	-1660
TD	3824	-1670

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing  
 8" 188  
 5" 3817  
 DST 3201-18/21", 12' M, BHP 830#  
 DST 3472-87/45", G/17", O/38",  
 BHP 1290#  
 DST 3526-36/30", 2040' G, 295'  
 O, 60' WTR, BHP 1320#  
 DST 3568-87/75", 150' OCM, BHP  
 350#

EGGER POOL DST 3641-52/30",  
 20' M, TR O, BHP 100#  
 CO TD: DD 3824: 3  
 BOPD, NATL/6 HR, NW:  
 ACID 500

+	+	+
+	+	+
+	+	+