

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PRT PERCORS

API Well Number: 15-195-20603-00-00

Spot: NWNWNE

Sec/Twnshp/Rge: 14-13S-21W

5074 ~~230~~ feet from S Section Line, 2310 feet from E Section Line

Lease Name: SCHMEIDLER

2375 Well #: 1

County: TREGO

Total Vertical Depth: 3849 feet

Operator License No.: 30717

Op Name: DOWNING-NELSON OIL CO INC

Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3843	0	180 SX
SURF	8.625	273	0	180 SX

125.09

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/25/2008 12:30 PM

Plug Co. License No.: 99977

Plug Co. Name: QUALITY OIL WELL CEMENTING

Proposal Rcvd. from: TERRY W. PIESKER

Company: DOWNING-NELSON OIL CO., INC.

Phone: (785) 735-4363

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 8 sxs gel - 300# hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/25/2008 1:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 125 sxs cement with 300# hulls - pumped 8 sxs gel.
Pumped 165 sxs cement with Max. P.S.I. 150#. Shut in.
Tied onto backside - pumped 7 sxs cement with Max. P.S.I. 150#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3843	3849		
3796	3800		
3787	3791		
3687			
3647			
3598	3600		
3546	3549		
3536	3538		
3496	3499		
3462	3465		
3444	3448		

INVOICED

DATE 20090600

INV. NO. 7-14-08

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3438.

Plugged through: CSG

District: 04

Signed

CM

(TECHNICIAN)

CM

Form CP-2/3


JUN 26 2008

PR

JOHN JAY DARRAH JR
 1010 CENTURY PLAZA BLDG #1 SCHMEIDLER 14-13-21W
 WICHITA, KS 67202 NW NW NE
 CONTR ABERCROMBIE DRILLING INC CTY TREGO

GEOL _____ FIELD HOMBURG

E 2167 KB CM 12/4/79 ^{CARD}ISSUED 2/7/80 IP P 23 BO & 27 BWPD
 ARB OH 3843-49
 API 15-195-20,603



LOG	TOPS	DEPTH	DATUM
*ANH		1535	+ 632
HEEB		3423	-1256
TOR		3443	-1276
LANS		3460	-1293
BKC		3734	-1567
MARM		3768	-1601
CHER SH		3806	-1639
ARB DOL		3838	-1671
RTD, LTD		3848	-1681
DDTD		3849	-1682
*SAMPLE TOP			

8-5/8" 273/180sx, 4 1/2" 3843/180sx
 DST (1) 3778-3810/30-30-30-60, 275'
 GIP, REC 370' GSY O, SIP 350' MO,
 SIP 787-696#, FP 76-246#, HP
 1905-1897#
 MICT - CO, (ARB OH) B/DRY W/GSO, FU
 25' MO, DD 3849 TD, ACIDIZED, WOULD
 NOT TAKE, CP 500#, SWB DWN & REC 500'
 0/40", SWB 7 BOPH, NW/3 HRS, 700' OFF
 BTM, POP, P AVER 23 BO. & 27 BWPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

20 1/2
 1000
 KONGHELL

1-27-81