

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22144-00-02  
Spot: SWNENWNE Sec/Twnshp/Rge: 5-15S-13W  
4720 feet from S Section Line, 1930 feet from E Section Line  
Lease Name: GROSS A Well #: 1  
County: RUSSELL Total Vertical Depth: 3175 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2960		
L1		3000		
PROD	5.5	3167	0	w/247 sxs cmt
SURF	8.625	684	0	w/330 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/23/2008 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: JASON OIL COMPANY, LLC Phone: (620) 727-3410

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Pull 1600' casing. Bridge plug 2960'. Liner 300' to 3250'. 103.19

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/23/2008 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Sanded at 2575' and dumped 5 sxs cement.  
Cut 5 1/2" - pulled to 1250' - pumped 125 sxs with 300# hulls.  
Pulled casing to 700' - pumped 170 sxs cement with 200# hulls - good circulation of cement.  
Topped off with 25 sxs cement - full.

Perfs:

Top	Bot	Thru	Comments
3084	3087		
2912	2916		

**INVOICED**  
DATE 7-14-08  
INV. NO. 2009060080

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 30 2008

CONSERVATION DIVISION  
WICHITA KS

Remarks: QUALITY OIL WELL CEMENTING-TICKET #2421.

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

Form CP-2/3

JUN 24 2008

*[Handwritten initials]*

HERMAN R. TRAPP

324 FRONT

RUSSELL, KS 67665

CONTR LAWBANCO DRILLING, INC.

#1 "A" GROSS

CITY RUSSELL

5-15-13W


560' ENL&

1930' FEL, NE/4

GEOL

FIELD

HALL-GURNEY



ELV 1727 KB SPD 6/11/83

CARD ISSUED

1/12/84

IP P 15 BO & 100 BWPD

1723 GL

LKC 2912-2916

API 15-167-22,144

DRLRS	Tops	Depth/Datum
ANH		685 + 1042
B/ANH		715 + 1012
NO OTHER TOPS AVAILABLE		
RTD		3175-1448

8 5/8" - 685/330 SX; 5 1/2" - 3166/247 SX  
 MICT - CO, PF (LKC) 2984-86, W / 4 SPF, AC 250G (15%), SWB LD, NON-COMMERICAL, SET BP AT 2970, PF (LKC) 2912-16, W / 4 SPF, AC 750G (1%), SWB LD, SO, RE-AC 3500G (28%), SWB LD, GSO, SET 2 7/8" TBG AT 2962, POP, P 15 BO & 100 BWPD (GR 40"), 8/10/83 TIGHT HOLE - NO OTHER INFO TO BE RELEASED AT PRESENT - WILL RELEASE INFO WHEN AVAILABLE - TEMP COMP - 1/12/84

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

560' ENL&

19-11-81