

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22478-00-00  
Spot: W2NE Sec/Twnshp/Rge: 33-15S-12W  
3960 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: FOX Well #: 1  
County: RUSSELL Total Vertical Depth: 3297 feet

Operator License No.: 6622 33813  
Op Name: SCHOENBERGER, J.L. DBA JASON OIL  
Address: 3718 - 183RD. ST. PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3294	0	w/250 sxs cmt
SURF	8.625	500	0	w/unknown sxs cmt <u>107.15</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2008 11:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: JASON OIL COMPANY Phone: (620) 727-3410

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2008 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality sanded off bottom 3190' - topped with 5 sxs.  
Cut casing at 1460' - pumped 100 sxs cement with 300# hulls.  
Pulled casing to 800' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 500' - pumped 40 sxs cement with 100# hulls.  
Pulled casing to 150' - pumped 50 sxs to circulate.  
Pulled casing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3252	3254		
3248	3250		

**INVOICED**  
DATE 7-14-08  
INV. NO. 2009060080

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JUL 02 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #1993.

Plugged through: CSG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

CM


Form CP-2/3

JUN 26 2008

*PS*

33-15-12W  
C W/2 NE

J.S. MARTIN OIL OPERATIONS #1 FOX  
 323 N. MAIN  
 HOTSTINGTON, KS 67544  
 CONTR BOGER BROTHERS DRILLING CTY RUSSELL  
 GEOL DAVID P. WILLIAMS FIELD HALL-GURNEY  
 ELV 1783 K B SPD 10/12/84 CARD ISSUED 1/24/85 IP P 10 BO & 3 BWPD  
 1778 GL CONG 3248-3254 OA



LOG	Tops	Depth/Datum
HEEB		2875-1092
TOR		2894-1111
DOUG		2906-1123
IATAN		2964-1181
LANS		2974-1191
BKC		3224-1441
CONG		3237-1454
SAND		NOT AVAILABLE
ARB		3278-1495
RTD&LTD		3297-1514

API 15-167-22,478  
 E 8 5/8 " 500, 5 1/2 " 3294/250SX  
 DST (1) 2875-2925 (SHAW, DOUG) / 30-30-30-30, REC 5' DM.  
 W/ OIL SPKS ON TOP OF TOOL, SIP 374-264#, FP 44-33 / 44-33#  
 DST (2) 3145-68 (LKC) / 45-45-45-45, REC 65' SW, NS, SIP  
 539-517#, FP 22-22 / 44-44#, HP 1593-1560#, BHT 126°  
 DST (3) 3220-50 (CONG) / 30-45-30-45, REC 600' FROGGY GSY  
 OIL, NW, SIP 810-712#, FP 66-132 / 189-231#, HP 1593-158#,  
 BHT 124°  
 MICT - CO, PF (CONG) 3252-54 & 3248-50, AC 500G (15%) SWB  
 DWN, SO, POP, P 10 BO & 3 BWPD 11/4/84 (GR 35.3°)