

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-30017-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 33-15S-1W  
4321 feet from S Section Line, 4416 feet from E Section Line  
Lease Name: MILLER B Well #: 2  
County: SALINE Total Vertical Depth: 2610 feet

Operator License No.: 33409  
Op Name: JONES, CHARLES  
Address: 2504 MERIDIAN  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2603		
SURF	8.625	132		

84.83

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/17/2008 11:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 654-8342

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 5 SXS CEMENT. PERFORATE CASING AT 200'.  
CIRCULATE CEMENT FROM 200' TO SURFACE.

Plugging Proposal Received By: DAVE WERTZ WitnessType: NONE  
Date/Time Plugging Completed: 06/17/2008 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report: SANDED TO 2563' AND CAPPED WITH 5 SXS OF CEMENT. PERFORATED PIPE AT 200' RAN TUBING TO 200 FT AND PUMPED 125 SXS CEMENT TO CIRCULATE TO SURFACE. PLUG FELL AND REQUIRED 15 SXS TO TOP OFF.

Perfs:  
**INVOICED**  
DATE 7-14-08  
INV. NO. 2009060081

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JUN 27 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: CONSOLIDATED TICKET #13747 TOTAL = 140 SXS 60/40 4% GEL  
Plugged through: CSG

District: 02

Signed Greg Eves  
(TECHNICIAN)