

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20811-00-00
Spot: E2NW Sec/Twnshp/Rge: 4-11S-33W
1200 feet from N Section Line, 1850 feet from W Section Line
Lease Name: NOLLETTE TRUST "A" Well #: 1-4
County: LOGAN Total Vertical Depth: 4820 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	322		240 SX

156.65

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/06/2008 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2435

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 06/06/2008 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2667' w/25 sxs.
2nd. Plug at 1647' w/100 sxs.
3rd. Plug at 375' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 7-14-08
INV. NO. 2009060083


RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

cm

Form CP-2/3

JUN 27 2008