

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23437-00-00  
Spot: SESENWSW Sec/Twnshp/Rge: 29-10S-21W  
1500 feet from S Section Line, 1200 feet from W Section Line  
Lease Name: NOAH Well #: 1-29  
County: GRAHAM Total Vertical Depth: 3990 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		

129.68

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2008 1:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: LARRY Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 06/25/2008 2:15 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3920' w/25 sxs.  
2nd. Plug at 1740' w/25 sxs.  
3rd. Plug at 930' w/100 sxs.  
4th. Plug at 260' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED  
DATE 7-14-08  
INV. NO. 2009060084

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Basye  
(TECHNICIAN)

CM

Form CP-2/3

JUN 30 2008

PKT